

```

{
  "playbook_id": "wifi_stadium",
  "version": "3.5",
  "system": "WiFi",
  "role": "WiFi Technician – Stadium",
  "location": "Stadium (Bowl, Sidelines, Locker Rooms)",
  "temporal_frame": ["M1", "M2", "M3", "M4", "M5", "M6"],
  "nin_phases": ["Discover", "Diagnose", "Design", "Deploy", "Debrief"],
  "tasks": [
    {
      "task_id": "WIFI_1.1",
      "sequence": 1,
      "description": "Verify stadium WiFi controller health: confirm all controllers are online,
licensed, and reporting normal status.",
      "nin_phase": "Diagnose",
      "milestone": "M3",
      "time_relative": "morning_game_day",
      "dependencies": [],
      "severity": "high",
      "required": true,
      "telemetry_required": true,
      "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
    },
    {
      "evidence_fields":
["controller_count", "controllers_healthy_flag", "timestamp_completed", "notes"]
    },
    {
      "task_id": "WIFI_1.2",
      "sequence": 2,
      "description": "Confirm all game-day SSIDs (public, operations, team, media,
IVRS-related) are broadcast and mapped to correct VLANs and QoS profiles.",
      "nin_phase": "Diagnose",
      "milestone": "M3",
      "time_relative": "morning_game_day",
      "dependencies": [],
      "severity": "high",
      "required": true,
      "telemetry_required": true,
      "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
    },
    {
      "evidence_fields": ["ssid_list", "ssid_validation_status", "timestamp_completed", "notes"]
    },
    {

```

```

    "task_id": "WIFI_1.3",
    "sequence": 3,
    "description": "Run AP health check: confirm all critical APs for bowl, sidelines, locker
rooms, and press/IR booths are online with acceptable signal and noise levels.",
    "nin_phase": "Diagnose",
    "milestone": "M3",
    "time_relative": "morning_game_day",
    "dependencies": [],
    "severity": "high",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
},
    "evidence_fields":
["aps_total", "aps_online", "aps_problem_list", "timestamp_completed", "notes"]
},
{
    "task_id": "WIFI_1.4",
    "sequence": 4,
    "description": "Validate RF profiles and channel plans for the bowl and sidelines to avoid
co-channel interference and align with league RF guidance.",
    "nin_phase": "Design",
    "milestone": "M3",
    "time_relative": "morning_game_day",
    "dependencies": [],
    "severity": "medium",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
},
    "evidence_fields":
["rf_profile_name", "rf_health_summary", "timestamp_completed", "notes"]
},
{
    "task_id": "WIFI_1.5",
    "sequence": 5,
    "description": "Confirm cart-mounted WiFi antennas are connected, aligned per FTR
standard, and associated APs are online with expected signal levels on both sidelines.",
    "nin_phase": "Diagnose",
    "milestone": "M3",
    "time_relative": "4h_before_kickoff",
    "dependencies": [],
    "severity": "high",
    "required": true,

```

```

    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
},
    "evidence_fields":
["home_cart_ap_status","visitor_cart_ap_status","timestamp_completed","notes"]
},

{
    "task_id": "WIFI_2.1",
    "sequence": 6,
    "description": "Run pregame WiFi throughput test at Home bench, Visitor bench, and
50-yard line seating using the game-day SSID used for operations; capture downlink, uplink,
and latency.",
    "nin_phase": "Diagnose",
    "milestone": "M3",
    "time_relative": "3h_before_kickoff",
    "dependencies": ["WIFI_1.1","WIFI_1.2","WIFI_1.3"],
    "severity": "high",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
},
    "evidence_fields":
["home_bench_down_mbps","home_bench_up_mbps","home_bench_latency_ms","visitor_benc
h_down_mbps","visitor_bench_up_mbps","visitor_bench_latency_ms","bowl_down_mbps","bow
l_up_mbps","bowl_latency_ms","timestamp_completed","notes"]
},
{
    "task_id": "WIFI_2.2",
    "sequence": 7,
    "description": "Run spot checks in locker rooms and IR booth to confirm strong signal and
authentication on the appropriate restricted SSIDs.",
    "nin_phase": "Diagnose",
    "milestone": "M3",
    "time_relative": "3h_before_kickoff",
    "dependencies": [],
    "severity": "medium",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
},
    "evidence_fields":
["locker_room_rssi_dbm","locker_room_auth_status","ir_booth_rssi_dbm","ir_booth_auth_status
","timestamp_completed","notes"]

```

```

    },
    {
      "task_id": "WIFI_2.3",
      "sequence": 8,
      "description": "Validate capacity thresholds and client load projections for bowl sections
expected to be at or near sellout.",
      "nin_phase": "Design",
      "milestone": "M3",
      "time_relative": "3h_before_kickoff",
      "dependencies": [],
      "severity": "medium",
      "required": true,
      "telemetry_required": true,
      "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
    },
    "evidence_fields":
["projected_clients_peak", "capacity_per_section", "risk_sections", "timestamp_completed", "notes"
]
  },

  {
    "task_id": "WIFI_3.1",
    "sequence": 9,
    "description": "Confirm WiFi monitoring dashboards (NMS, controller views) are
configured with alerts for AP down, high channel utilization, and excessive authentication
failures.",
    "nin_phase": "Design",
    "milestone": "M4",
    "time_relative": "2h_before_kickoff",
    "dependencies": [],
    "severity": "high",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress", "Complete", "Fail"]
  },
  "evidence_fields": ["alert_policies_enabled", "timestamp_completed", "notes"]
},
{
  "task_id": "WIFI_3.2",
  "sequence": 10,
  "description": "Record pregame WiFi readiness status in EVERGAME GDA system,
including any known risk areas and mitigation actions.",
  "nin_phase": "Deploy",
  "milestone": "M4",

```

```

    "time_relative": "90m_before_kickoff",
    "dependencies": ["WIFI_2.1","WIFI_2.2","WIFI_2.3"],
    "severity": "high",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
  },
  "evidence_fields": ["evergame_status","risk_summary","timestamp_completed","notes"]
},

{
  "task_id": "WIFI_4.1",
  "sequence": 11,
  "description": "During pregame gate opening window, monitor live WiFi client counts,
throughput, and channel utilization for bowl and concourses; adjust RF or power if thresholds
exceed safe limits.",
  "nin_phase": "Deploy",
  "milestone": "M4",
  "time_relative": "gates_open",
  "dependencies": ["WIFI_3.1"],
  "severity": "high",
  "required": true,
  "telemetry_required": true,
  "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
},
  "evidence_fields":
["client_count_peak","utilization_hotspots","changes_applied","timestamp_completed","notes"]
},
{
  "task_id": "WIFI_4.2",
  "sequence": 12,
  "description": "During game, actively monitor for AP failures or severe performance
degradation in any high-priority area (benches, locker rooms, IR booth) and log incidents/punch
list items in EVERGAME.",
  "nin_phase": "Deploy",
  "milestone": "M5",
  "time_relative": "in_game",
  "dependencies": ["WIFI_3.1"],
  "severity": "high",
  "required": true,
  "telemetry_required": true,
  "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
},
  "evidence_fields": ["incident_log_ids","timestamp_completed","notes"]

```

```

    },
    {
      "task_id": "WIFI_4.3",
      "sequence": 13,
      "description": "Respond to operations requests from FTR, C2P, IR Tech, or IVRS for
WiFi-related troubleshooting on carts or field systems.",
      "nin_phase": "Deploy",
      "milestone": "M5",
      "time_relative": "in_game",
      "dependencies": [],
      "severity": "medium",
      "required": true,
      "telemetry_required": false,
      "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
    },
    "evidence_fields": ["support_requests_count","timestamp_completed","notes"]
  },

  {
    "task_id": "WIFI_5.1",
    "sequence": 14,
    "description": "Postgame, export WiFi performance summary (client counts, throughput,
error rates) and attach to EVERGAME game record.",
    "nin_phase": "Debrief",
    "milestone": "M6",
    "time_relative": "postgame",
    "dependencies": [],
    "severity": "medium",
    "required": true,
    "telemetry_required": true,
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]
  },
  "evidence_fields": ["report_link","timestamp_completed","notes"]
},
{
  "task_id": "WIFI_5.2",
  "sequence": 15,
  "description": "Review and close any WiFi-related punch list items that can be resolved
same day; mark remaining items for follow-up in GMS and EVERGAME.",
  "nin_phase": "Debrief",
  "milestone": "M6",
  "time_relative": "postgame",
  "dependencies": ["WIFI_4.2"],
  "severity": "medium",

```

```
    "required": true,  
    "telemetry_required": true,  
    "state_machine": { "initial": "Open", "allowed_transitions": ["In Progress","Complete","Fail"]  
  },  
  "evidence_fields":  
  ["items_closed_count","items_remaining_count","timestamp_completed","notes"]  
}  
]  
},
```